



# UNIVERSITY OF HYDERABAD

{Established by the act of Parliament in 1974}

University Works Department,  
University of Hyderabad,  
Gachibowli,  
P.O. Central University,  
HYDERABAD – 500 046.  
Dated: 23.12.2019

No. UH/Engg/NIQ/2019-20/

## NOTICE INVITING QUOTATION

Quotations are invited from the registered Contractors for the following work at University of Hyderabad Campus.

S. No.	Name of the work	Estimated Cost Rs.	D.D. should be drawn in favour of Finance Officer, UoH. EMD Rs.	Time for Completion of the work
1	1 <sup>st</sup> Recall: Maintenance of buildings: Brick work at gas room side and CC flooring in corridors at LVGH Kitchen in University of Hyderabad campus	Rs.2,25,200/-	Rs. 4,504/-	45 Days
2	1 <sup>st</sup> Recall: Maintenance of buildings: Replacement of floor tiles and other minor repair works at A-14 Quarter and providing roofing sheets to Servant Quarter in University of Hyderabad campus	Rs.2,79,500/-	Rs.5,590/-	01 Month

**NOTE:-** The contractors/bidders are requested to download the General Conditions and Eligibility criteria for submission of quotation documents from the University website from 24.12.2019 and submit under envelop system. The submission and opening of quotations details as follows.

- Date of submission of Quotations : 03.01.2020 up to 2.30 P.M.
- Date of opening of Quotations : 03.01.2020 up to 3.00 P.M.

Sd/-  
EXECUTIVE ENGINEER

**General Conditions & Eligibility Criteria for Submission of Quotation:**

1. The contractor shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The copies of relevant certificates of Income tax/IT returns, PAN no valid registered certificate and Experience certificate successfully completed Civil works of all relevant certificates and shall sign all the pages of Technical & price bid without fail.
3. The Contractors are requested to draw demand draft towards EMD separately as per the work wise drawn in favour of Finance Officer, University of Hyderabad payable at Hyderabad.
4. Statutory taxes/Deductions shall be made as per rules.
5. The competent authority on behalf of the University of Hyderabad does not bind itself to accept the lowest or any other quotation and reserves to itself the authority to reject any or all the quotations received without the assignment of any reason. All quotations in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.
6. Work to be carried out in the presence under supervision of UWD.
7. The site shall be made available as and when required for execution of work.
8. Canvassing whether directly or indirectly, in connection with tenderers is strictly prohibited and the quotations submitted by the contractors who resort to canvassing will be liable to rejection.
9. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's compensation Act.
- 10 This work order can be cancelled and the work can be stopped at any time by the Officer-in- charge of the work or by any officer superior to him in authority.
- 11 The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
- 12 If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done if University provides water.
- 13 Seigniorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

**Sd/-  
EXECUTIVE ENGINEER**

- 14 The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit**. The EMD becomes part of Security Deposit. The deposit is liable to be forfeited to the University for Non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
- 15 Defect liability period of **Six (06) Months** commences from the date of satisfactory completion of the work.
- 16 For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty will be levied. If work is delayed the University reserves right to foreclose rescind the work, without risk and cost and get the balance work done departmentally through any other contractor, and the contractor shall have no right to claim any compensation on this account.
- 17 In case, the work cannot be started due to reasons not within the control of the contractor within 1/8th of the stipulated time for completion of work, either party may close the contract. In such eventuality, the Earnest Money Deposit of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable at all.
- 18 The Contractor should ensure while executing the work that there should be no deviation beyond permissible limit & variation.
- 19 The work of each item to be executed in consultation with the user Department.
- 20 In case of execution of any extra / alternation / changes, the total amount may not exceed sanctioned amount; if it exceeds the prior approval may be taken from the User Department and Competent Authority.
- 21 Assistant Engineer (Civil)/Assistant Engineer (Electrical) has to enclose the work completion certificate and **No claim certificate** from the contractor along with the final bill.
- 22 Work satisfactory certificate from user department and or Engineer in charge may be obtained before submission of bills for payment.
- 23 Further details can be had from the Office of the University Engineer, University of Hyderabad, Hyderabad-5000 046 during working hours.
- 24 GST invoice form should be filled and submitted along with the bill.
- 25 The Labour engaged and working equipment brought by the contractor for the work shall be recorded in the UoH Security main gate before entering in to the premises and obtain necessary gate pass.

**Sd/-**  
**EXECUTIVE ENGINEER**

## 28 SPECIALISED AGENCIES

### 28.1 CIVIL

1	Water proofing compound :	proof/impermo/scott no.1/ Duroseal/ Excot/ Pidilite/Cico/Sikka/Fosroc.
2	Pressed steel frames for doors:	a) M/s. Diwni Door Systems/Steel windows/ ventilators,
		b) M/s. Roshini Steels Pvt.Ltd.
		c) M/s. Elegant Products Ltd.
3	Sections of Aluminium doors:	Jindal/Crown/Jyothi/Prestige/ Mowjee/ Garg. Partitions etc. Jindal/Crown/Jyothi/Prestige/Mowjee/Garg. Partitions etc.
4	Aluminium anodized fittings	Crown/Jindal/Jalal/ESS & ESS
5	Steel doors / windows / Ventilator and fittings	Crown/Jyothi/Prestige/ Shalimar/ Classic/Argent
6	Flush doors/plywood shutters Board	Anand/Kitply/Novapan/Deco/Mysore Chip
7	Glazing	Modi Guard, Hindustan St. Gobain
8	Door Closers, Floor springs	Everite /any ISI mark
9	Paint and Distempers	Asian, Nerolac
10	Waterproof cement	Snowcem India Ltd./Berger/Asian/ Durocem
11	Paint wood/ Steel Primer Asian/ Shalimar synthetic enamel paint	Jenson Nicholson (Dorocac)/ (Apcolite) (superlac) Berger (Luxol)
12	Ceramic glazed tiles	Nitco/Kajaria/Johnson/Regency
13	Reinforcement	SAIL, Visaka/ Tisco, Rashtriya Ispat Nigram
14	Cement	A.C.C, L & T, Birla, C.C.I
15	Structural Steel	TATA/JINDAL/ SAIL / ISPAT NIGAM

Sd/-  
**EXECUTIVE ENGINEER**

**Name of work: Maintenance of Buildings:- Replacement of floor tiles and other minor repair works at A-14 Quarter and providing roofing sheets to Servant Quarter" in UoH campus.**

- 1) Comparative statement for Quoted rates shall be based on rates exclusive of GST.  
 2) L-1 shall be decided based on quoted rates exclusive of GST.  
 3) The Bidder should quote rates exclusive of GST and may quote GST percentage separately. The GST shall be reimbursed on submission of proof by them.

**SCHEDULE OF QUANTITIES**

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.25	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead	180.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
2	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.	47.50 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm				
3	11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	189.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
4	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete	39.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
5	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	11.00 Cum	cum	Figure: Rs _____ Words: Rupees _____	
6	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.43 Cum	cum	Figure: Rs _____ Words: Rupees _____	
7	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :				
	17.60.1	100 mm inlet and 100 mm outlet				
	17.60.1.2	Sand Cast Iron S&S as per IS: 1729	2.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
8	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	1.00 No.	each	Figure: Rs _____ Words: Rupees _____	

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
9	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan ) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1.00 No.	each	Figure: Rs _____ Words: Rupees _____	
10	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :	6.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
	18.49.1	15 mm nominal bore				
11	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
	17.7.7	White Vitreous China Flat back wash basin size 450x 300 mm with single 15 mm C.P. brass pillar tap	2.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
12	14.85	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	4.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
13	9.135	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete.	25.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
	9.135.2	With 12 mm mild steel U beading				
14	18.22	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :	2.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
	18.22.1	100 mm diameter				

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
15	14.28	Providing and fixing brass curtain rods of wall thickness 1.25 mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete.	18.00 Meters	rmt	Figure: Rs _____ Words: Rupees _____	
	14.28.1	20 mm diameter.				
16	9.96	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :	2.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
	9.96.1	300x16 mm				
17	9.97	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete :	4.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
	9.97.4	150x10 mm				
18	9.100	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :	4.00 Nos.	each	Figure: Rs _____ Words: Rupees _____	
	9.100.1	125 mm				
19	15.28	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of:	12.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
	15.28.2	Asbestos sheet				



S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
20	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	20.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
21	6.4	Brick work with best locally available bricks in superstructure above plinth level up to floor V level in all shapes and sizes in :	0.55 Cum	cum	Figure: Rs _____ Words: Rupees _____	
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)				
22	13.12	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) finished rough with sponge including providing chicken mesh on junction of columns & beams & providing grooves where ever required as per instructions of Engineer-in-Charge.	25.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
23	10.26	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.				
	10.26.1	M.S. tube	92.00 Kgs	kg	Figure: Rs _____ Words: Rupees _____	

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
24	14.45	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :	130.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
	14.45.1	Old work (one or more coats)				
25	14.54	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	35.00 Sqm	sqm	Figure: Rs _____ Words: Rupees _____	
	14.54.1	One or more coats on old work				
26	MR	Supplying and fixing / replacement of health faucet (Make: Hindware/Equivalent)	1.00 No.	each	Figure: Rs _____ Words: Rupees _____	
					<b>Total Amount in figures Rs.</b>	
		<b>Less Rebate Offered if any</b> _____ <b>Net Amount</b> _____ <b>Total Amount in words(Rupees)(Excluding GST)</b> _____ <b>Add GST</b> _____ <b>Total Amount in words(Including GST)</b> _____				
1) Comparative statement for Quoted rates shall be based on rates exclusive of GST. 2) L-1 shall be decided based on quoted rates exclusive of GST. 3) The Bidder should quote rates exclusive of GST and may quote GST percentage separately. The GST shall be reimbursed on submission of proof by them. 4) The HSN Code for each item should be indicated.						
						<b>Contractor</b>